

NOTE: BORE ALL PAVED STREETS AND DRIVEWAYS
 Minimum depth requirements for crossings of state highways and county roads is 60".
 Minimum depth requirements for crossings of city streets and township roads is 48".
 Minimum depth for parallel installations on state highways and county roads is 36".
 Minimum depth for parallel installations on city streets and township roads is 30".
 All steel pipe welds to be coated with 2 part epoxy.

INSTALL LOCATING POINTS AT A MAXIMUM SPACING OF 1,000 FT.

INSTALL 2" PE CL-6
 JOINT TRENCH ~ DUAL MAIN ~ IN 10' UTILITY EASEMENT

E = INSTALL 2" 90 DEG ELL
 T = INSTALL 2" PE TEE

Install; Clean and Test; and Put in Service; Proposed new main per CenterPoint Energy Construction and Service Manual.

Purge new main until essentially 100% gas reading is obtained on Combustible Gas Indicator. See CenterPoint Energy Construction and Service Manual Section CS-B-1.230 for purging mains into service.

Install a marker ball at a new end of main, at a valve, at each ell of a horizontal offset, at road crossings and at any fitting or pressure control identified as needing to be located in the future. Refer to CenterPoint Energy Construction and Service Manual section CS-B-1.310 for installation procedures.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the state of Minnesota.

Signature: _____

Typed or Printed Name: Casey Tollefson

Date: _____ License Number: 52693

PROPOSED:
 2" PE END CAP 83898175-2018
 SQUEEZE OFF & REMOVE END CAP
 INSTALL:
 2" PE TEE
 EXTEND:
 2" PE CL-6 E & S
 JT IN 10' UE

EXISTING:
 2" PE END CAP 86344120-2018
 @ 26' NCL 86 AVE
 59' ECL FORESTVIEW LN
 11' N & 4' E CURB
 36" COVER
 SQUEEZE OFF & REMOVE END CAP
 INSTALL:
 2" 90 DEG ELL E
 EXTEND:
 2" PE CL-6 E
 JT IN 10' UE

INSTALL MAIN 83898175-2018
 PRIOR TO MAIN 87944813-2018



MINNESOTA REGION

PROPRIETARY AND CONFIDENTIAL

PROJECT #: 87944813

M52900 MAPLE GROVE

ONE CALL:

Hennepin
 *SE14 T119/R22
 * = this Page

LEGEND:

- ACTIVE MAIN
- DESIGNED MAIN
- PROPOSED ABANDONED/ OUT OF SERVICE MAIN
- ABANDONED/ OUT OF SERVICE MAIN
- EXISTING MAIN
- PROPOSED MAIN 83898175-2018 2" PE CL-6
- 4" PVC CONDUIT CROSSING TWO REQUIRED

PIPE REQUIRED:
 1515' 2" PE CL-6

1515' PIPE

PROPOSED ABANDONED PIPE:

COPIES:
 PIPELINE INTEGRITY PACKET: N
 STATION MANAGER: N
 DD NUMBER: N
 CORROSION: N
 EMP: N

FOLLOW INTERNAL PIPE SAMPLING REQUIREMENTS?
 SURVEYOR REQUIRED?
 RETURN PACKET TO ENG?
 GFIP#: N
 PERMITS: MAPLE GROVE


PROJECT DESCRIPTION: NBRE MILLS CREEK2 PH2

DESIGNER: Wendy Kronwall
 PHONE #: 612-321-5508
 DRAWN BY: Wendy Kronwall
 DESIGN DATE: 11/6/2018

REVISION INFO:

Main
 SS#

SCALE 1" = 100'
 SHEET 1 OF 1



EXISTING:
 2" PE END CAP 86344120-2018
 @ 32' NCL 86 AVE
 25' ECL DEERWOOD LN
 1' N & 37' E CURB
 36" COVER
 SQUEEZE OFF & REMOVE END CAP
 BUTT FUSE AND EXTEND:
 2" PE CL-6 N
 JT IN 10' UE

DESIGNER EXPRESS DESIGN

11/6/2018 2:49:07 PM