


**MICHELS TO INSTALL SERVICE
FIELD SERVICES TO INSTALL METER**

METER WO# 92922930
 INSTALL 7MTC OUTSIDE METERSET (CL-6)(LOAD: 7,000cfh)
 ON BOARD FOR TEMP HEAT W/ 2" CS820 REGULATOR
 @5PSI W/ 1/2" ORIFICE W/ 1" 289H RELIEF @6PSI ON A 2"
 MPT x 2" IPS ANODELESS RISER W/ BYPASS.
 PERMANENT METER WILL BE AN 11MTC @2PSI.
 MTRSET EQUIP# 15348523

SERVICE WO# 92922931
 INSTALL: 6" X 2" IPS PE SVC TEE W/ 1.8" TAP. INSTALL
 2" IPS PE 10,000cfh EFV IN BLVD. INSTALL 195' OF 2"
 IPS PE CL-6 SVC LINE W/ 2" MPT x 2" IPS ANODELESS
 RISER W/ BYPASS, W/SLEEVE.
 SERVICE EQUIP# 65199824

When butt fusing to existing in-service polyethylene, visually inspect for the presence of hydrocarbon permeation immediately after removing fusion iron. If any bubbling is identified on the heated surface, do not join to new PE pipe. Allow to cool and cut this end off (12" length) and send to the Golden Valley Lab with street location and W.O. #. Complete tie-in/extension using an electrofusion coupling(s). Document in field notes.

Project area cleared for internal impacts. Pipe being removed is unregulated for disposal if coating does not exist or is non-asbestos. Refer to CNP Construction and Service Manual CS-B-1.110, CS-B-1.330, and CS-B-1.100, for pipe to be abandoned.

CenterPoint Energy 

PROPRIETARY AND CONFIDENTIAL

92922931
 M52900 MAPLE GROVE

ONE CALL:
 Hennepin
 *SW30 T119/R22
 * = this Page

LEGEND:

- ACTIVE
- DESIGNED
- PROPOSED
- ABANDONED
- ABANDONED (A)

- Interruptible
- Existing
- Normal
- Future
- Proposed

Address: 18695 73rd Ave N
 Customer: CBS Construction Svcs
 Contact Person: John Gran
 Contact Phone: 612-369-0965
 Sales Rep: Shelly Houde
 Sales Rep Phone: 320-808-8630
 Construction Hotline: 612-321-5310
 Copies To Pipeline Integrity: No
 Curb Valve: No
 Copies to Corrosion: No
 Corrosion Approval: N/A
 Follow Internal Pipe Sampling Requirements? No
 Permits: Yes - Hennepin Cnty
 Requested Install Date: 3/15/20 or earlier

Approval: _____

PROJECT DESCRIPTION:
 HAVENWOOD OF MPL GRV

DESIGNER: Wendy Seidl
PHONE #: 612-321-5476
DRAWN BY: Wendy Seidl
DESIGN DATE: 2/5/2020

Revised Print
 Destroy All Others
 Revision History
 Date:
 Description:
 Design Approval:

IC Services
 SCAN DATE: 1" : 101'
 SHEET 1 OF 1

DESIGNER EXPRESS DESIGN
 2/5/2020 4:50:18 PM

